

I-25 La Bajada - (MP 264 to MP 267.5) Slope Mitigation and Roadway Improvements

2024 Southwest Geotechnical Conference

May 22, 2024

Presentation Team - Outline

- I-25 La Bajada - Milepost 264 to Milepost 267.5
 - Project Team/Details
 - Derek Meier, PE – , Senior Project Manager, Wilson & Company, Inc.
 - Geotechnical History
 - Melissa Bates, PE – Geotechnical Engineer, NMDOT Geotechnical Section
 - Geotechnical Analysis/Slope Mitigation/Construction
 - Michael Pegnam, PE – Senior Geotechnical Engineer, WSP USA, Inc.

Project Team

Owner =



Designer =



Contractor =




Project Limits



- I-25 La Bajada – Milepost 264 to Milepost 267.5
 - Geotechnical analysis – slope mitigation measures
 - Roadway reconstruction –
 - Fill in the depressed median and build a concrete wall barrier to divide NB/SB lanes
 - Accommodate for a future 3rd driving lane in the SB direction
 - Drainage improvements –
 - Larger concrete rundowns
 - Replace and/or extend existing pipes
 - Install parallel storm drain system to capture seepage flows
 - Safety improvements –
 - Extended the entrance/exit ramps at Cochiti (Exit 264)
 - Intelligent Transportation System (ITS) was installed


Existing Roadway Section

- Three northbound lanes, two southbound lanes
- Depressed median
- Cable barrier separates traffic



Design Roadway Section

- Addition of future third southbound lane
- Concrete wall barrier (CWB) will replace cable barrier
- New metal barrier



- I-25 La Bajada – Milepost 264 to Milepost 267.5
 - Design (CN 5101340) was awarded in September 2019 and completed in January 2022
 - Construction (CN 5101341) was bid/let in February 2022
 - Mountain States Constructors, Inc. was awarded project for a cost of \$39.9M
 - Construction (CN 5101341) NTP was issued in March 2022

- I-25 La Bajada – Milepost 264 to Milepost 267.5
 - MSCI started site work in July 2022
 - Geo-Solutions, Inc (GSI) mobilized and installed test columns in Oct. 2022
 - Full-scale In-Situ Soil Mixing (SM) began in November 2022
 - SM of the southbound lanes was completed in January 2023
 - SM of the northbound lanes was completed in November 2023
 - The parallel storm drain system was installed in February 2024
 - The northbound driving lanes paving completed in March 2024
 - Overall project completion anticipated for May 31st, 2024

Geotechnical History




Geotechnical

- Undulations and pavement cracking
- Sealing and patching
- Starting in the shoulder and moving into the traffic lanes




- Vertical displacement and voids
- Deeper than just a pavement problem




- Erosion downslope
- Cracks = water entry points




Geotechnical – Original 1950's Era Highway




Geotechnical – Widening in the 1980's



Geotechnical – Widening Construction



Geotechnical – Inclinometers




- Six inclinometers (extending 37 to 62 ft. below ground) installed behind the southbound (downslope side) guardrail
- Probe fed down a slotted pipe
- Data collected monthly
- Inclinometer #4 shows the most downslope movement



Geotechnical – Inclinometer Data – Creep Movement



Data for Inclinometer #4

- Approx. 5/8 inch cumulative over 4 years
- Starts around the interface between native and fill
- Possible seasonal trends (monsoon season and winter)




Wilson & Company, Inc., Engineers &


La Bajada 4A - Direction of Max. Displacement (148 degrees)



La Bajada 4B - Perpendicular to Max. Displacement (58 degrees)



Geotechnical – Causes of Surficial Pavement Distress



- Issues related to fill and possibly drainage
- Both horizontal and vertical movement components



Geotechnical Analysis/Mitigation Design

Geotechnical Investigation Timeline

- 1996/1998 – 12 boreholes drilled by NMDOT
- 2013 – 7 cone penetration tests
- 2017 – 6 inclinometer boreholes installed along southbound lanes
- 2020 – 16 hollow-stem auger/HQ3 core boreholes
- 2020 – 4 MASW profiles along edge of southbound and northbound lanes



Geotechnical – Field Investigation

> 50 tsf is preferred = 250 tsf constrained modulus – typical of compacted embankment




Geotechnical – Field Investigation


> 50 tsf is preferred




CPT-02





CPT-07



Geotechnical – Field Investigation





Geophysics - MASW



Geotechnical – Field Investigation

Shear strength Tests – Torsional Ring Shear and Direct Shear




Geotechnical – Designed Mitigation: Soil Mix Columns

Potential Failure Surface

Southbound Lanes

Northbound Lanes



- Numerous options considered
- Shallow repairs such as excavation and replace do not fix the deep problem areas
- Repair must address both potential instability and settlement of fill


Geotechnical – Deep Soil Mixing Method to Create Columns

- Paddles mix soil in place
- Water/cement slurry injected during mixing
- Result is “soilcrete” columns
- Columns are much stiffer and stronger than surrounding soil
- Prevent settlement of the roadway embankment
- Stabilize potential sliding failure surfaces




Geotechnical – Geosynthetic Reinforced Soil Platform

- Platform to support roadway and transfer load into the columns
- Layers of strong, high-density polypropylene (PP) geogrids
- Layers of compacted road base (aggregate) material



Geotechnical – Geosynthetic Reinforced Soil Platform



NOT TO SCALE


2
2-10

GEOGRID LOAD TRANSFER PLATFORM PROFILE

Design Methods

1


Column-Supported Embankment



Filz et al. GeoGrid Bridge (2012)

2


Tensioned Membrane



Giroud et al. Method (1990)


3

Stiffened Geogrid Beam



Collin (2003)



Geotechnical – Soil Mix Column Design



- Finite Element Modeling using Rocscience RS2
- Geogrid modeled as Geotextile Structural Interface Element
- Soil Mix columns modeled as a slip joint between soil and grout
- Softening of elements between columns to determine beam action
- Also checked differential settlement using Geogrid Bridge Spreadsheet



Geotechnical – Soil Mix Column Design

- Displacements contained within LTP under traffic loads



Geotechnical – Soil Mix Column Design


- Beam action of LTP maintained with minimal settlement over “softened” zones



Geotechnical – Soil Mix Column Design

Final area replacement ratio of 15%


- limits differential settlement to ~1/4-inch
- Achieves average modulus value of compacted embankment



Construction

- I-25 La Bajada – Milepost 264 to Milepost 267.5
 - Construction (CN 5101341) NTP was issued in March 2022
 - Mountain State Constructors, Inc. (MSCI) started site work in July 2022
 - Geo-Solutions, Inc (GSI) mobilized and installed test columns in Oct. 2022.

Construction - Test Program



Pilot Test Program
10/20/22-10/22/22

SANTA FE, NM
GEO-SOLUTIONS PROJECT #22-014

DRAWN BY **AMRG 22JUN2022**

CHECKED

APPROVED

PROPERTY OF GEO-SOLUTIONS, INC.
IMPORTANT: THIS DRAWING PRINT IS LOANED FOR MUTUAL ASSISTANCE AND AS SUCH IS SUBJECT TO RECALL AT ANY TIME. INFORMATION CONTAINED HEREON IS NOT TO BE REPRODUCED OR REPRODUCED IN ANY FORM FOR THE IDENTIFICATION OF PARTS, OTHER THAN NECESSARY SUBCONTRACTORS AND SUPPLIERS WITHOUT THE WRITTEN CONSENT OF GEO-SOLUTIONS, INC.

SEAL

DATE

REVISIONS

REV	DESCRIPTION
(a)	Revised: _____ Check: _____ Appr.: _____
(b)	Revised: _____ Check: _____ Appr.: _____
(c)	Revised: _____ Check: _____ Appr.: _____

SHEET 1 OF 1

Drawing Name
GSI ISS Layout.dwg

Construction - Test Program

- 8 different grout mixes were tested during test program
- Grout mix for full scale production chosen to achieve the design strength with a factor of safety



Construction - Test Program

- Wet grab samples collected, and cores completed



Figure 2 – Sampling Tool



Construction - Test Program

- Wet grab samples collected, and cores completed



Construction - Grout production



- Portland cement delivered to site in pneumatic tankers
- Water provided by MSCl and stored in frac tanks
- Metered out by weight then pumped to SM rigs.

Construction - Soil Mixing Rigs


- Delmag rig can reach a maximum depth of 42 feet below ground surface



Construction - Soil Mixing Process





- Auger is advanced through layers of material
- Swell removed to make room for stabilized material
- After depth has been reached, column is stroked several times to ensure homogenization.
- On-board monitoring equipment ensures all depth intervals receive adequate grout



Construction - Soil Mixing Completion


- 547 Columns Completed in Phase I (SB Lanes)
- 414 Columns Completed in Phase 2 (NB Lanes)



Construction - Boulder Obstructions

Obstructions encountered during soil mixing

- Within median
- around drainage structures



Construction - Boulder Obstructions

- Buried rock excavation debris from previous widening
- Shallow refusal of SM columns
- Solution: additional columns to minimize voids spanned by LTP



Construction – Load Transfer Platform

- Tensar TriAx TXSW geogrid reinforcement
- Overlaps of 4 feet and 2 feet in the directions of roll length, roll width



Construction - Paving Operations

Project substantial completion date: May 31, 2024

Long-term settlement monitoring at two locations: SAAV and TEPC



NMDOT
I-25 La Bajada
Slope Mitigation

Thank you!